


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

McPherson County. Sec. 28 Twp. 21 Rge. (E) 3W (W)
Location as "NE/CNW/SW" or footage from lines SW SW SW
Lease Owner Homer Krehbiel
Lease Name Schroeder Well No. 1
Office Address McPherson, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed November 29 1964
Application for plugging filed " 1964
Application for plugging approved " 1964
Plugging commenced " 1964
Plugging completed " 1964
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3557 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	303'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

heavy mud	3557' to	300'	RECEIVED STATE CORPORATION COMMISSION
wooden plug @		300'	
20sx cement on plug			DEC 23 1964
heavy mud	to	40'	
10sx cement on plug			CONSERVATION DIVISION Wichita, Kansas
surface soil	5' to	0'	

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Melland Drilling Co., Inc.
Address Box 783, McPherson, Kansas

STATE OF Kansas, COUNTY OF McPherson, ss.
Donald J. Melland (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Donald J. Melland
Box 783, McPherson, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of December, 1964

My commission expires December 23, 1967

Frank S. Melland
Notary Public.

WELL RECORD

LEASE: Schroeder

WELL NO. 1

ELEVATION: 1466 RB

LOCATION: SW SW SW
Sec. 28-21-3W

COMMENCED: 11/11/64

COMPLETED: 11/29/64

OPERATOR: Homer Krehbiel

CONTRACTOR: Melland Drilling Company, Inc.
Post Office Box 783
McPherson, Kansas

CASING RECORD: 8 5/8" @ 303' / 220sx

FORMATION	LOG
clay	40
sand	190
shale & shells	305
shale & shells	445
anhydrite	635
lime & shale	1050
shale	1870
lime & shale	2210
sand	2380
shale	2403
lime & shale	2930
shale & lime	2980
lime & shale	3070
shale	3107
Mississippi	3258
shale	3520
lime	3557
RTD	3557
Sample Tops	
Lansing	2456
Mississippian	3107
Kinderhook	3259
Maquoketa	3403
Viola	3520
Simpson, Sand	3546

FORMATION

LOG

DST #1 3115-3142, open 1 hr., gas in
44 min. rec. 100' gas cut mud & 60'
muddy water, BHP 578-624, FP 37-73DST #2 3540-3551, open 20 min. weak
blow for 1 min., rec., 10 feet of mud
BHP 597- 514, FP 9-9

RECEIVED
STATE CORPORATION COMMISSION
DEC 23 1964
CONSERVATION DIVISION
Wichita, Kansas

CERTIFICATE

State of Kansas, County of McPherson, ss.

I, Donald J. Melland, do hereby certify that the above is a true and correct copy of the log
of the above named and described well, as reflected by the records of the Melland Drilling Company, Inc.

Donald J. Melland

Subscribed and sworn to before me, a Notary Public, in and for the County of McPherson, State of Kansas,

this 8th day of December, 1964My Commission expires: December 23, 1967

Frank J. Miller
_____ Notary Public