

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. 8 Twp. 21 Rge. 11 (X) West (W)

Location as "NE/CNW/SW" or footage from lines SE/4 SW/4 NE/4
Lease Owner WIDENER-HAHN F. G. Holl
Lease Name WIDENER-HAHN Well No. 2
Office Address 6427 East Kellogg, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed Oct. 11 19 68
Application for plugging filed same 19 68
Application for plugging approved " 19 68
Plugging commenced " 19 68
Plugging completed 10-11 19 68
Reason for abandonment of well or producing formation _____

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes - Ralph Warren

Name of Conservation Agent who supervised plugging of this well Ralph Warren
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3450 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole full with mud - Set plug at 600'
With pump truck, pump 40 sacks ~~mix~~ cement thru drill pipe.
come up the hole to 300', spotted 25 sacks cement thru drill pipe.
come up to 40', good bridge with 10 sacks cement
2 sacks cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION
OCT 14 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____
Address _____

STATE OF Kansas, COUNTY OF Barton, ss.
Larry Curtis (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Larry Curtis
Box 823 - Great Bend, Ks
(Address)

SUBSCRIBED AND SWORN to before me this 12th day of October, 19 68

My commission expires 4-11-70

Alroy M. Hague
Notary Public.

DRILLERS'
WELL LOG

DATE COMMENCED: October 3, 1968
DATE COMPLETED: October 11, 1968

F. G. Holl
WIDENER-HAHN #2
SE/4 SW/4 NE/4
Sec. 8-T21s-11w
Stafford Co., Kansas

1789
ELEVATION: 1889 K.B.

0	-	250'	Surface Clay & Sand
250	-	544'	Red Bed & Shale
544	-	570'	Anhydrite
570	-	995'	Shale
995	-	1545'	Shale & Lime Shells
1545	-	2100'	Lime & Shale
2100	-	2600'	Shale & Lime
2600	-	2996'	Lime & Shale
2996	-	3000'	Shale
3000	-	3015'	Lime & Shale
3015	-	3030'	Lime
3030	-	3122'	Shale
3122	-	3127'	Lime
3127	-	3144'	Shale
3144	-	3384'	Lime
3384	-	3400'	Shale
3400	-	3413'	Chert
3413	-	3428'	Shale
3428	-	3450'	Dolomite

FORMATION TOPS

Anhydrite	544
Heebner	2996
Toronto	3015
Brown Lime	3122
Lansing Kansas City	3144
BASE K.C.	3384
Chrt	3400
Simp. Shale	3413
Arbuckle	3428
R.T.D.	3450

SURFACE PIPE: Set new, 20#
8-5/8" pipe at 250' with
225 sacks cement with 2% gel.

A F F I D A V I T

State of Kansas
County of Barton) ss.

Larry Curtis, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Subscribed and sworn to before me this 12 day of October, 1968.

My Comm. Expires:
4-11-70

Larry Curtis

Kathleen M. Hague

Notary Public

RECEIVED
STATE CORPORATION COMMISSION
OCT 14 1968
CONSERVATION DIVISION
Wichita, Kansas