

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-22,198.0000

LEASE NAME Rohar

WELL NUMBER 4-8

SPOT LOCATION E/2 E/2 E/2

SEC. 8 TWP. 21 RGE. 11 (W)

COUNTY Stafford

Date Well Completed 3-23-85

Plugging Commenced 12:01 AM
3-23-85

Plugging Completed 1:45 AM
3-23-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR F. G. Holl

ADDRESS 6427 East Kellogg
Wichita, Kansas 67207

PHONE # (316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District No. 1

Is ACO-1 filed? If not, is well log attached? Yes

Producing formation Depth to top bottom T.D. 3560'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	308'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Filled hole with heavy mud plugged through open ended drill pipe;
50 sacks at 720'; 50 sacks at 510'; 50 sacks at 330'; 1/2 sack
balls, plug and 10 sacks at 40'; 15 sacks in rathole. Used 60/40 Pozmix,
2% gel and 3% cc.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142
Address P. O. Box 129
Sterling, Kansas 67579

RECEIVED
STATE CORPORATION COMMISSION

STATE OF KANSAS COUNTY OF RICE, ss.

MAR 28
3-28-1985

F. A. Wuellner (employee of operator) or CONSERVATION DIVISION
(operator) of above-described well, being first duly sworn on oath, says: That Wichita, Kansas
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

STERLING DRILLING COMPANY

(Signature) F. A. Wuellner

(Address) P. O. Box 129, Sterling, Ks 67579



SUBSCRIBED AND SWORN TO before me this 25 day of March, 1985.

My Commission expires: 4-6-85

Agnes D. Wurst
Notary Public

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG ----- ROHAR #4-8

Located: C E/2 E/2 E/2, Section 8-21S-11W, Stafford County,
Kansas

OWNER: F. G. Holl

ROTARY DRINNING CONTRACTOR: Sterling Drilling Company

COMMENCED: March 18, 1985

COMPLETED: March 23, 1985

TOTAL DEPTH: 3560'

LOGCASING RECORD

0 - 170	Surface Soil and Sand	Ran 7 joints new 8 5/8", 23# casing. 296.23' pipe set at 308' K.B.
170 - 225	Clay, Shale	Cemented with 250 sacks 60/40 Pozmix with 3% cc. Plug down at 5:30 PM, 3-18-85, by Howco.
225 - 311	Red Bed	
311 - 534	Shale, Sand, Red Bed	
534 - 3560	Lime and Shale	Plugged.

Deviation Surveys: 0° at 311'
 3/4° at 3175'
 1° at 3560'