

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15.185.12153.0000

API NUMBER _____

LEASE NAME Kasselman "A"

WELL NUMBER #3

SPOT LOCATION C E/2 W/2 NW/4

SEC. 8 TWP. 21 RGE. 11 or W

COUNTY Stafford

Date Well Completed 3/18/62

Plugging Commenced 10/2/84

Plugging Completed 10/2/84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Okmar Oil Company

ADDRESS 970 Fourth Financial Center, Wichita, KS 67202

PHONE # 316, 265-3311 OPERATORS LICENSE NO. 5245

Character of Well SWD
(Oil, Gas, D&A, SWD Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District 1 - Dodge City

Is ACO-1 filled? No If not, is well log attached? Yes

Producing formation Arbuckle Depth to top 3434' bottom 3510' T.D. 3510'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Arbuckle	Oil	3434'	3446'	4 1/2"	3475'	None
N/A		0	286'	8 5/8"	286'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state the character of same and depth placed, from feet to feet each set. Ran tubing to 320'.

Pump 125 sax cement, circulated cement, pulled tubing. Pump another 125 sax down casing through swedge. Had 125# standing pressure on cement. Cut 8 5/8" off below surface and filled cellar in.

Witnessed by Steve Durant and Bud Metz from KCC/KDHE.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Okmar Oil Company License No. 5245

Address Box 723, Hays, KS 67601

RECEIVED
STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Sedgwick, ss.

OCT 10 1984


Melvyn D. Abels (employee of operator) of CONSERVATION DIVISION
(operator) of above-described well, being first duly sworn on oath, says: That Wichita, Kansas
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

(Signature) Melvyn D. Abels

(Address) 970 Fourth Financial Center
Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 9th day of October, 1984

Cecelia A. Bowser
Notary Public



My Commission expires: August 5, 1987

DRILLER'S WELL LOG

DATE COMMENCED: March 11, 1962
 DATE COMPLETED: March 18, 1962

Fred D. Asbury
 KASSELMAN "A" #3
 C E/2 W/2 NW/4
 Stafford County, Kansas

0 - 225	Clay & Sand
225 - 579	Red Bed
579 - 598	ANHYDRITE
598 - 1535	Shale and shells
1535 - 2100	Lime - Shale
2100 - 2345	Shale
2345 - 2765	Shale & Lime
2765 - 3014	Lime
3014 - 3029	Shale & Lime HEEBNER
3029 - 3048	Lime TORONTO
3048 - 3142	Shale DOUGLAS
3142 - 3402	Lime LANSING
3402 - 3434	Sand & Shale SIMPSON
3434 - 3510	Dolomite ARBUCKLE
3510	R.T.D.

ELEVATION: 1818 K.B.

FORMATION DATA:

ANHYDRITE	579
HEEBNER	3014
BROWN LIME	3142
LANSING	3162
SIMPSON	3402
ARBUCKLE	3434
R.T.D.	3510

SURFACE CASING: Set 280' of
 8-5/8" casing @ 280' with 200
 sacks cement.

PRODUCTION CASING: Set 3477'
 of 4 1/2" pipe @ 3475 with 125
 sacks cement.

A F F I D A V I T

STATE OF KANSAS
 COUNTY OF BARTON) ss

Lewis O. Chubb of lawful age does swear that the facts and statements
 herein contained are true and correct to the best of his knowledge.

Lewis O. Chubb

Subscribed and sworn to before me this 21st day of March, 1962.

Clair E. Stinson
 Clair E. Stinson-NOTARY PUBLIC

My Commission Expires: June 24, 1963.

RECEIVED
 STATE CORPORATION COMMISSION

OCT 10 1984

CONSERVATION DIVISION
 Wichita, Kansas