

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15.185.20168.0000

LEASE NAME Widener-Hahn

WELL NUMBER #3

SPOT LOCATION 100' N of SE/4 SW/4 SE/4

SEC. 8 TWP. 21 RGE. 11W (E) or (W) (W)

COUNTY Stafford

Date Well Completed _____

Plugging Commenced 6-9-86

Plugging Completed 6-25-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Duke Drilling Co., Inc.

ADDRESS Box 823 Great Bend, Kansas 67530

PHONE # (316) 793-8366 OPERATORS LICENSE NO. 5929

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 3511'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	249'	none
				4-1/2"	3510'	2726'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 3375' and 4 sacks cement. Shot pipe @2900', 2726', pulled a total of 84 joints of 4-1/2" casing. Plugged surface with 2 hulls, 15 gel, 50 cement, 10 gel, 1 hull, plug and 120 cement, 60/40 pos, 6% gel. Plugging Complete.

(if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050
Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(employee of operator) Wichita, Kansas

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347 Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 27th day of June, 1986



Irene Hoover
Notary Public

My Commission expires: _____

DRILLERS' WELL LOG

DATE COMMENCED: April 14, 1969
 DATE COMPLETED: April 21, 1969

F. G. Holl
 WIDENER-HAHN #3
 100' No. of SE/4 SW/4 SE/4
 SECTION 8-T21S-R11W
 Stafford County, Kansas

0 - 191' Sand
 191 - 544' Red Bed
 544 - 566' ANHYDRITE
 566 - 1370' Shale & Shells
 1370 - 2150' Lime & Shale
 2150 - 2700' Shale & Shells
 2700 - 3005' Lime
 3005 - 3009' Shale
 3009 - 3024' Lime & Shale
 3024 - 3030' Lime
 3030 - 3131' Shale
 3131 - 3149' Lime & Shale
 3149 - 3396' Lime
 3396 - 3404' Congl.
 3404 - 3419' Sand
 3419 - 3448' Shale
 3448 - 3474' Sand
 3474 - 3511' Shale

ELEVATION: 1783 K.B.

FORMATION DATA

ANHYDRITE	544
HEEBNER	3005
TORONTO	3024
DOUGLAS	3030
BROWN LIME	3131
LANSING	3149
Base K.C.	3396
CONGL. SAND	3404
2nd SAND	3448
RTD	3511

SURFACE PIPE: Set new 8-5/8"
 at 249' w/225 sacks cement.

PRODUCTION STRING: Set new
 4 1/2" at 3510' with 600 gallons
 latex.

A F F I D A V I T

STATE OF KANSAS
 COUNTY OF BARTON) ss.

Larry Curtis, of lawful age does state that the facts and
 statements herein contained are true and correct to the best of his
 knowledge.

Subscribed and sworn to before me this 28th day of April, 1969.

My Comm. Expires:
4-11-70

Larry Curtis
 Notary Public

FILED
 STATE CONSERVATION COMMISSION
 JUN 06 1966
 CONSERVATION DIVISION
 Wichita, Kansas