

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15,185,20119.0000

LEASE NAME Rohar

WELL NUMBER 2

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 8 TWP. 21 SRGE. 11 W (R) or (W)

COUNTY Stafford

Date Well Completed

Plugging Commenced 3/13/90

Plugging Completed 3/23/90

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR F.G. Holl Company

ADDRESS P.O. Box 158 Belpre, KS. 67519

PHONE#(316) 995-3171 OPERATORS LICENSE NO. 5056

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filed? If not, Is well log attached?

Producing Formation Depth to Top Bottom T.D. 3412'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|---------|------|----|-------|--------|------------|
| | | | | 8 5/8 | 230' | none |
| | | | | 4 1/2 | 3400' | 2800' |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Sanded bottom to 3350' ran 4 sacks cement. Shot pipe @2800'.
Plugged with 4-hulls, 10-gel, 50 cement, 10-gel, 1-hull,
100 sacks cement 60/40 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: F.G. Holl Company

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) *R. Darrell Kelso*

(Address) P.O. Box 347 Chase, KS. 67524


RECEIVED
STATE CORPORATION COMMISSION

3-28-1990

WITNESSED AND SWORN TO before me this 26 day of March, 19 90

CONSERVATION DIVISION
Wichita, Kansas
My Commission Expires:

James Herzberg
Notary Public



W E L L L O G

DATE COMMENCED: July 11, 1968
 DATE COMPLETED: July 18, 1968

F. G. Holl
 ROHAR #2
 NW/4 NE/4 SE/4
 SEC. 8-T21-R11W
 Stafford County, Kansas

0 - 202 Sand
 202 - 540 Red Bed
 540 - 563 Anhydrite
 563 - 1235 Shale & Shells
 1235 - 1615 Shale & Lime
 1615 - 1800 Lime w/Shale
 1800 - 2195 Lime & Shale
 2195 - 2515 Shale w/lime
 2515 - 2745 Lime & Shale
 2745 - 2855 Lime
 2855 - 2993 Lime w/Shale
 2993 - 3105 Shale
 3105 - 3136 Shale & Lime
 3136 - 3383 Lime
 3383 - 3397 Conglomerate
 3397 - 3410 Sand
 3410 - 3412 Shale
 3412 RTD

ELEVATION: 1784 K.B.

FORMATION TOPS

| | |
|--------------|------|
| Anhydrite | 540 |
| Heebner | 2993 |
| Douglas | 3026 |
| Brown Lime | 3118 |
| Lansing | 3136 |
| Conglomerate | 3383 |
| Simpson Sand | 3397 |
| RTD | 3412 |

SURFACE CASING: Set: 8-5/8",
 new, 20# casing at 230' w/
 300 sacks cement.

PRODUCTION CASING: Set
 new 4 1/2" casing at 3400'
 w/100 sacks pozmix - 1/4#
 flowseal per sack.

A F F I D A V I T

STATE OF KANSAS
 COUNTY OF BARTON) ss

Larry Curtis, of lawful age, does swear and state that the facts
 and statements contained herein are true and correct to the best of his
 knowledge.

Larry Curtis

Subscribed and sworn to before me this 22 day of July, 1968

My Commission Expires:
April 11, 1970

Verity M. Hague
 Notary Public

RECEIVED
 STATE CONSERVATION COMMISSION

MISSOURI KANSAS
 CONSERVATION COMMISSION

JAN 9 1990

JAN 9 1990

CONSERVATION DIVISION
 Wichita, Kansas

STATE CONSERVATION
 RECEIVED