

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Stafford County. Sec. 8 Twp. 21 Rge. 11 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW-NE-NE NE NW-NE

Lease Owner F.G. Holl
Lease Name Scheufler Well No. B-1


Office Address 6427 East Kellogg- Wichita, Kansas 67207
Character of Well (Completed as Oil, Gas or Dry Hole) oil

Date Well completed March 18 19 63
Application for plugging filed September 18 1980
Application for plugging approved 19
Plugging commenced September 25 1980
Plugging completed September 30 1980

Reason for abandonment of well or producing formation depleted
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well WM. T. Owen
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
			287'	8 5/8"	287'	none
			3435'	4 1/2"	3435'	2589.76'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom hole plug, sand to 3200' with 4 sacks cement.

Used Allied cementing pumped, 8 sacks hulls, 25 gell, 125sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Glenns Casing Pulling Inc. Box 413 Ellinwood, Kansas 67526


STATE OF Kansas COUNTY OF Barton, ss.
LAVon Glenn (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

(Signature)

Ellinwood, Kansas
(Address Kansas)

SUBSCRIBED AND SWORN TO before me this 2nd day of October, 1980



My commission expires _____

Jenny Kasselmann
Notary Public.

RECEIVED
STATE CORPORATION COMMISSION
OCT - 3 1980
CONSERVATION DIVISION

WELL LOG

Date Commenced **March 11, 1963**

Date Completed **March 18, 1963**

F. C. Hill
MINERALS & PETROLEUM
Sec. B-21-114
Stafford County, Kansas

Elevation 1793 K.F.

0' - 40'	Surface Sand
40' - 180'	Sand & Clay
180' - 270'	Redbed
270' - 547'	Redbed
547' - 575'	ANHYDRITE
575' - 1195'	Shale & Limestone
1195' - 1360'	Salt & Shale
1360' - 1766'	Limestone & Shale
1766' - 1781'	Sand
1781' - 2010'	Lime & Shale
2010' - 2540'	Shale & Limestone
2540' - 2736'	Lime & Shale
2736' - 2993'	Lime TOPEKA
2993' - 3000'	Shale MEEBNER
3000' - 3030'	Limestone & Shale
3030' - 3120'	Shale DOUGLAS
3120' - 3140'	Limestone REDDEN LIMESTONE
3140' - 3384'	Limestone & Shale LANSING
3384' - 3402'	Chert & Shale CONGLOMERATE
3402' - 3416'	Shale
3416' - 3435'	Dolomite ARBUCKLE

FORMATION DATA

Anhydrite	547	(-1245)
Meebner	2993	(-1200)
Toronto	3016	(-1226)
Douglas	3030	(-1223)
Isan	3120	(-1327)
Lansing	3140	(-1347)
Conglomerate	3384	(-1591)
Arbuckle	3416	(-1623)
R. I. D.	3435	(-1642)

Surface Casing: Set 257' of 8 5/8" casing @ 287' with 200 sacks cement.

Production Casing: Set 3435' of 4 1/2" casing @ 3435' with 600 gals. latex cement.

AFFIDAVIT

State of Kansas County of **Redick**

I, **Irue Knowles**, Geologist, do swear that the statements and matters herein contained are true to the best of my knowledge.

F. C. Hill

By

Irue Knowles
Geologist

Subscribed and sworn to before me this 26th day of March, 1963.

My Commission Expires Jan. 31, 1967

Pat Lendrum
Notary Public

STATE RECEIVED
MINERALS & PETROLEUM COMMISSION
SEP 19 1960
CONSERVATION DIVISION
Wichita, Kansas