

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Commission

P. O. Box 17027
Wichita, Kansas 67217

WELL PLUGGING RECORD

| | | | |
|--|---|--|--|
| | X | | |
| | | | |
| | | | |
| | | | |

Locate well correctly on above
Section Plat

Stafford County, Sec. 6 Twp. 21 Rge 11 (E) W (W)
 Location as "NE/CNWESW" or footage from lines NE NE NW
 Lease Owner Spector Pipe & Supply Inc.
 Lease Name Dannebohn Well No. #1
 Office Address P. O. Box 169 ; Russell, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) _____
 Date well completed 10-13-61 19____
 Application for plugging filed April 12, 1974
 Application for plugging approved April 15, 1974
 Plugging commenced April 30, 1974
 Plugging completed May 3, 1974
 Reason for abandonment of well or producing formation failure to produce
 profitable

If a producing well is abandoned, date of last production 19____
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Russell Biberstein
 Producing formation Arbuckle Depth to top 3419 Bottom 3499 Total Depth of Well 3500 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8" | 271 | None |
| | | | | 4 1/2" | 3499 | 2829 |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

April 30, 1974 Plugged off bottom. Dumped sand to 3100'. Mixed and dumped 4 sx of cement.

May 3, 1974 Plugged off top. Allied Cementing Co. mixed and pumped down 8 5/8" surface casing, 2 sx of hulls, 10 sx of gel and 100 sx of cement.

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 5 1974
 CONSERVATION DIVISION
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor, RUSS CASING PULLING, INC.
 Address P. O. Box 1082 ; Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Russell ss.
 Spector Pipe & Supply, Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
 (Address) Wichita, Kansas

Subscribed and Sworn to before me this 4th day of June, 1974

My commission expires May 21, 1975

Wilma M. Lindahl
 Notary Public.

15.185.19528.0000

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


COPY

Company- DUKE DRILLING CO. ET AL
Farm- Dannebohm No. 1

SEC. 6 T. 21 R. 11W
NE NE NW

Total Depth. 3500'
Comm. 10-6-61 Comp. 10-13-61
Shot or Treated.
Contractor.
Issued. 1-20-62

County Stafford
KANSAS



CASING:
8 5/8" 271' cem w/200 sx.
4 1/2" 3499' cem w/600 Gal. Latex

Elevation. 1814' KB

Production. 55 BOPD

Figures Indicate Bottom of Formations.

| | |
|-------------------------|------|
| clay, sand | 90 |
| clay | 150 |
| sand | 195 |
| red bed | 572 |
| Anhydrite | 592 |
| red bed | 1115 |
| shale & lime | 1420 |
| lime & shale | 1665 |
| shale & lime | 2780 |
| lime | 3000 |
| shale Heebner | 3004 |
| shale & lime | 3019 |
| lime Toronto | 3031 |
| shale Douglas | 3124 |
| lime, shale, Brown Lime | 3141 |
| lime Lansing | 3379 |
| Conglomerate | 3398 |
| shale Simpson | 3419 |
| dolomite, Arbuckle | 3500 |
| Total Depth | |

RTD

TOPS:

| | |
|----------------|------|
| Base Anhydrite | 590 |
| Heebner | 3005 |
| Toronto | 3020 |
| Douglas | 3036 |
| Brown Lime | 3128 |
| Lansing | 3143 |
| Conglomerate | 3380 |
| Simpson Shale | 3400 |
| Arbuckle | 3419 |

RECEIVED
STATE CORPORATION COMMISSION
APR 15 1974
CONSERVATION DIVISION
Wichita, Kansas