

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-20,686.0000

LEASE NAME Donnabaugh

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #1

4290 Ft. from S Section Line

2310 Ft. from E Section Line

LEASE OPERATOR Smith Oil Operations

SEC. 6 TWP. 21 RGE. 11 (X) or (W)

ADDRESS P.O. Box 550, Hutchinson, Kansas 67504-0550

COUNTY Stafford

PHONE# (316) 663-6622 OPERATORS LICENSE NO. 6988

Date Well Completed 1961

Character of Well Oil

Plugging Commenced 8/24/90

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8/24/90

The plugging proposal was approved on 8/14/90 (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? N/A If not, Is well log attached? N/A

Producing Formation Arbuckle Depth to Top _____ Bottom _____ T.D. 3500

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|---------|------|------|-------|--------|------------|
| | | 0 | 258 | 8 5/8 | 258 | 0 |
| | | 0 | 3498 | 4 1/2 | 3498 | 2500 |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
1st plug sanded back to 3390' and dumped 4 sx cement on top of sand through bailer.
2nd plug ran tubing to 810', pumped 6 sx gel and 200 lbs. hulls, layed down 7 joints of tubing and circulated cement to surface with 200 sx cement.
Tubing stuck from 590-150'.

(If additional description is necessary, use BACK of this form.)

REMARKS: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 2500' of 4 1/2" casing.

Name of Plugging Contractor Kizzar Well Servicing License No. 7686

Address P.O. Box 346, Chase, Kansas 67524

SEP 24 1990

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Smith Oil Operations

STATE OF Kansas COUNTY OF Reno, ss.

Dale R. Ohi

(Employee of Operator) or (~~Operator~~) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Dale R Ohi

(Address) P.O. Box 550, Hutchinson, Kansas 67504-0550


SUBSCRIBED AND SWORN TO before me this 21st day of September, 1990

Mary Johnson

Mary Johnson

Notary Public

Commission Expires: 7-15-94





Kansas Corporation Commission

MIKE HAYDEN GOVERNOR
KEITH R. HENLEY CHAIRMAN
RICH KOWALEWSKI COMMISSIONER
MARGALEE WRIGHT COMMISSIONER
JUDITH McCONNELL EXECUTIVE DIRECTOR
FRANK A. CARO, JR. GENERAL COUNSEL

District # 1
304 W. McArtor
Dodge City, Ks 67801
(316) 225-6760

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

MEMORANDUM

TO:

FROM: Steve Durrant

DATE: August 27, 1990

SUBJECT: Donnabaugh #1
SW NW NE 6-21S-11W
Stafford County

The original well plugging application was submitted by Robert Reed. He pulled casing and abandoned the well. Richard E. Smith took over and plugged it on 8/24/90.

RECEIVED
STATE CORPORATION COMMISSION
AUG 29 1990
CONSERVATION DIVISION
Wichita, Kansas