


Give All Information Completely.  
Make Required Affidavit  
Mail & Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

WELL PLUGGING RECORD



Stafford County, Sec. 6, Twp. 21, Rge. 11 (E) (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE $\frac{1}{4}$  SW $\frac{1}{4}$  NE $\frac{1}{4}$   
Lease Owner The Veeder Supply and Development Company  
Lease Name Peterson "G" Well No. 2  
Office Address Cherryvale, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed January 4 19 53  
Application for plugging filed January 4 19 53  
Application for plugging approved January 4 19 53  
Plugging commenced January 4 19 53  
Plugging completed January 4 19 53  
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19...  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives  
Producing formation... Depth to top... Bottom... Total Depth of Well 3513 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
		0	316'	8/ 5/8"	316'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from... feet to... feet for each plug set.

Set Bridge plug at 240'. Put 20 sacks cement on plug through drill pipe. Filled with mud to 35'. Set Bridge plug at 35'. Put 10 sacks cement to surface.

1-24-1953

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 24 1953

Name of Plugging Contractor Buick Drilling Inc.  
Address Box 331, St. John, Kansas  
(If additional description is necessary, use BACK of this sheet)

CONSERVATION DIVISION  
Wichita, Kansas

STATE OF Kansas, COUNTY OF Montgomery, ss.  
Floyd W. Hild (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Floyd W. Hild  
Cherryvale, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 23rd day of January, 19 53  
Leo Lawson Notary Public.

My commission expires July 11, 1956  
23-8390-s 6-51-20M

PLUGGING  
WELL SEC 6 T 21 R 11  
70-37

Veeder Supply &amp; Dev'l. Co.



Cherryvale, Kansas

Drilled for Veeder Supply and Development Co. Farm Peterson "A" No. 2 Depth 3513'  
 Contractor Buick Drilling Inc. Pipe 316' 8 5/8"  
 Location SE SW NE Sec. 6 Twp. 21 Range 11  
 Commenced 12-21-52 Completed 1-4-53 County Stafford State Kansas

Sand and Gravel	0	180	
Sand, Clay and Sandy Shale	180	240	
Shale	240	280	
Red Bed	280	565	
Anhydrite	565	605	
Shale and Shells	605	930	
Salt and Shale	930	1160	
Shale and Shells	1160	1465	
Lime and Shale	1465	2600	
Lime	2600	2690	
Lime and Shale	2690	3265	
Lime	3265	3305	
Lime and Shale	3305	3465	
Conglomerate	3465	3486	
Arbuckle Lime	3486	3513	T. D.

AFFIDAVIT

STATE OF KANSAS )  
 Montgomery County ) SS

Floyd W. Hild, of lawful age, being duly and solemnly sworn on oath says:

I am a resident of Cherryvale, Montgomery County, Kansas, and I hereby know and on oath state that the above drilling log covering the Peterson "A" #2 well in Section 6-21-11, Stafford County, Kansas, is true and correct. Further affiant saith not.

THE VEEDER SUPPLY & DEVELOPMENT COMPANY

By: Floyd W. Hild.

Subscribed and sworn to before me this 23rd day of January, 1953.

Leo Lawson  
 Notary Public

My commission expires: July 11, 1956

RECEIVED  
 STATE COMPLETION COMMISSION

JAN 24 1953

CONSERVATION DIVISION  
 Wichita, Kansas

**PLUGGING**  
 FILE SEC 6 T 21 R 1124  
 BOOK PAGE 70 LINE 37

**REMITTANCE**

15.185.12214.0000

Jan 8 19 53

TO State Corp. Co. Inc. 61414

800 Pittsburg Bldg. Wichita, Kan

\$ 25.00

ENCLOSED FIND DRAFT CHECK NO. 17560

FOR THE SUM OF Seventy five DOLLARS  
IN PAYMENT OF THE FOLLOWING INVOICES:

DATE OF BILL	AMOUNT	OVERCHARGE	SHORTAGE	GOODS RET'D	FREIGHT	DISCOUNT	NET
	<u>Shipping Fee (Pittsburg) A-2 Well</u>						

REMARKS: \_\_\_\_\_

REMITTED BY: \_\_\_\_\_

Veeder Supply & Dev. Co.  
Cherryvale, Kansas