


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Stafford County, Sec. 6 Twp. 21S Rge. 11E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
150' SW NE NE NW

Lease Owner Poor Boy Corporation
Lease Name Dannebohm B Well No. 1
Office Address RR #2, Ellinwood, Kansas 67526
Character of Well (Completed as Oil, Gas or Dry Hole)
oil



Locate well correctly on above
Section Plot

Date Well completed May 2 1977
Application for plugging filed July 20 1979
Application for plugging approved 19
Plugging commenced July 21 1979
Plugging completed July 31 1979
Reason for abandonment of well or producing formation
depleted

If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3500'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
			285'	8 5/8"	285'	none
			3498'	4 1/2"	3498'	2689.78

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded back to 3400' and dumped 4 sacks of cement.

Sun Oil Well Cementing, Inc. plugged well pumping in 8 sacks of hulls, 25 sacks of gel and 100 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION

AUG - 9 1979


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor PIPE PULLERS, INC.
Box 128, Ellinwood, Kansas 67526

STATE OF KANSAS COUNTY OF BARTON, ss.
Evelyn Roth (employee of owner) or (owner-or-operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth
Ellinwood, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of August, 1979



Jenny Kasselmann
Notary Public.

My commission expires

15.195.20726.0000

K. T. WOODMAN
RES. PHONE 733-0418
OFF. PHONE 265-7650
WICHITA, KANSAS

D. J. IANNITTI
PHONE 792-2921
GREAT BEND, KANSAS

WOODMAN & IANNITTI DRILLING COMPANY

Rotary Drilling Contractors

1008 DOUGLAS BUILDING
104 S. BROADWAY
WICHITA, KANSAS 67202

May 6, 1977

Company;	Poor Boy Corporation
Farm;	Donnebohm "B" #1
Location;	150' SW NE NE NW
Section;	6-21S-11W
County;	Stafford
Contractor;	Woodman & Iannitti Drilling Co.
Comm;	April 25, 1977
Compl;	May 2, 1977
Casing;	8 5/8 @ 285 w/225 sacks
	4 1/2 @ 3498 w/125 sx.

Figures Indicate Bottom Of Formations:

190	Sand
250	Shale & sand streaks
285	Red bed
610	Anhy
870	Red bed
1385	Shale
1460	Shale & lime
1825	Shale & lime
1965	Lime & shale
2325	Lime
2425	Lime
2675	Lime & shale
2830	Lime
3045	Lime & Shale
3205	Lime & shale
3255	Lime
3454	Lime
3500	Lime

I certify the above to be a true and correct copy of the driller's log to the best of my knowledge and belief.

Woodman & Iannitti Drilling Co.

K. T. Woodman
RECEIVED
K. T. STATE CORPORATION COMMISSION

JUL 23 1979

*Plug set at 3452 top w/very speedy line
Top Perf. at 3429*

CONSERVATION DIVISION
Wichita, Kansas