


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Flat

Stafford County. Sec. 6 Twp. 21 Rge. 11 (E) (W)
Location as "NE/CNW/SW" or footage from lines W/2 W/2 NW/4
Lease Owner Penguin Petroleum, Inc.
Lease Name Ringering Well No. 1
Office Address 709 Petroleum Bldg.
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed 2-26 19 51
Application for plugging filed 2-26 19 51
Application for plugging approved 2-26 19 51
Plugging commenced 2-27 19 51
Plugging completed 3-4 19 51
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	250	None
				5 1/2	3402	2960

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sand dumped to fill hole to 3270'
@ 5270' 5 sx cement dumped w/bailer
Hole mudded to 250'
Rock bridge from 250' to 240'
@ 240' dumped 15 sx cement
mudded hole to 30'
10 sx cement to bottom of cellar

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to W. G. Talbott
Address 709 Petroleum Building Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick ss.
B. D. Strickland (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *B. D. Strickland*
709 Petroleum Building
(Address)

SUBSCRIBED AND SWORN to before me this 28th day of March

Sumner E. Talbott
Notary Public
MAR 30 1951

My commission expires Oct 27, 1954

PLUGGING
FILE SEC 6 T 21 R 11 W
BOOK PAGE 64 LINE 3

CONSERVATION DIVISION
Wichita, Kansas

Company: Penguin Petroleum, Inc.

Farm: Ringering #2

Comm: February 11, 1951

Comp: February 22, 1951

Contractor: Penguin Petroleum, Inc.

Casing: 5 1/2" @ 3402' Cem. w/60 sx.

Sec 6, T 21 S, R 11 W
 1320 NL, 330 WL NW/4
 Stafford County, Kansas
 Rotary Tools
 Elevation: 1825'
 Rotary Total Depth: 3509'

0-250	Surface
-505	Red bed
-615	Red bed & shale
-645	Anhydrite
-940	Red bed & shells
-1000	Shale & shells
-1200	Shale
-1465	Shale & shells
-1600	Shale & shells
-1825	Shale & sandy lime
-1925	Lime & shale brk
-2550	Lime & shale
-2570	Shale & lime
-2745	Lime & shale
-2845	Shale & lime
-2982	Lime
-3140	Shale & lime
-3235	Lime & shale
-3417	Lime
-3480	Lime & shale
-3505	Conglomerate
-3509	Arbuckle

R.U.S.T. 3509' R.T.D.

Tops: Topeka	@ 2740'
Heebner	@ 5013'
Kansas City	@ 3157'
Arbuckle	@ 3505'

Certified to be a true copy of the well log as indicated on daily drilling reports.

PENGUIN PETROLEUM, INC.

By W.S. Talbot

Subscribed and sworn to before me, the undersigned, a Notary Public in and for Sedgwick County, Kansas, this 8th day of March, 1951.

My Commission Expires:

October 13, 1952

L. D. Hankland
 Notary Public

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 30 1951
 CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC 6 T21 S11 W
 BOOK PAGE 64 LINE 3