

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County. Sec. 6 Twp. 21S Rge. 11 (E) ^{XX} (W)

Location as "NE/CNWxSWx" or footage from lines SE SE SE

Lease Owner Veeder Supply & Development Co.

Lease Name Diets Well No. 4-"A"

Office Address Box 201, Cherryvale, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed January 25 19 55

Application for plugging filed January 25 19 55

Application for plugging approved January 25 19 55

Plugging commenced January 25 19 55

Plugging completed January 25 19 55

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Pratt, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3526 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	237'	
				Cemented w/150 sacks cement		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged at 137' with 20 sacks cment, plug at 35' with 10 sacks cement; heavy mud to 137'; heavy mud to 35', filled hole to top

JAN 21 1955

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Veeder Supply and Development Company
Address P. O. Box 201, Cherryvale, Kansas

STATE OF Kansas, COUNTY OF Montgomery, ss.
Floyd W. Hild (employee of owner) or ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Floyd W. Hild
Cherryvale, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of January, 19 55

My commission expires July 11, 1956
Leo Lawson Notary Public.

24-7368-9 3-53-20M

PLUGGING
FILE SEC 6 T 21 R 11W
BOOK PAGE 94 LINE 6

Veeder Supply & Dev'l. Co.



Cherryvale, Kansas

Drilled for Producers Pipe & Supply, Veeder Supply Farm & Dev'l. Co. Louis Kahan Diets No. 4-A Depth 3526'
 Contractor Veeder Supply & Dev'l. Co. Pipe 237' 8 5/8" csg. cemented W/150 sacks cement
 Location SE SE SE Sec. 6 Twp. 21S Range 11W
 Commenced 1-14-1955 Completed 1-25-1955 County Stafford State Kansas

Sand and clay	0	30	30
Sand, gravel, shale	30	195	165
Red bed, shale	195	560	365
Shale, shells	560	1410	850
Lime and shale	1410	1780	370
Shale	1780	1900	120
Lime	1900	1950	50
Shale, lime shells	1950	2040	90
Lime, shale	2040	2260	220
Shale, shells	2260	2440	180
Lime, shale	2440	2640	200
Lime	2640	2790	150
Lime, shale	2790	2880	90
Lime	2880	2898	18
Lime, shale	2898	3158	260
Lime	3158	3240	82
Broken lime	3240	3245	5
Lime, shale	3245	3310	65
Lime	3310	3335	25
Broken lime	3335	3382	47
Lime, shale	3382	3415	33
Lime, shale, chert	3415	3438	23
Lime, shale	3438	3456	18
Lime	3456	3470	14
Lime, shale	3470	3491	21
Lime, chert	3491	3526	35
Total Depth	3526		

Dry and plugged

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 21 1955
 CONSERVATION DIVISION
 Wichita, Kansas

AFFIDAVIT

STATE OF KANSAS)
 Montgomery County) SS

Floyd W. Hild, of lawful age, being first duly sworn on oath, deposes and says:

THAT he is a resident of Cherryvale, Montgomery County, Kansas; that he knows and hereby on oath states that the above drilling log covering the Diets #4-"A" Well located in Section 6-21S-11W, Stafford County, Kansas, is true and correct. Further affiant saith not.

THE VEEDER SUPPLY AND DEVELOPMENT CO.

By Floyd W. Hild
 Floyd W. Hild

Subscribed and sworn to before me this 29th day of January, 1955.

Les Lawson
 Notary Public

My commission expires July 11, 1956.

PLUGGING
 FILE SEC 6 T 21 R 11W
 BOOK PAGE 94 LINE 6