

~~No~~ KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

AUG 8 1963

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Petroleum Operating Co.

Complete Address: Box 7027, Tulsa, Oklahoma

Lease Name Keenan Well No. # 1

Location SE NW SE Sec. 30 Twp. 21 Rge. 13 (E) (W)W

County Stafford Total Depth 3742

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Sholom Drilling Co.

Address: Box 7027, Tulsa, Oklahoma License No.     

Operation Completed: Hour 1:00PM Day 3rd Month August Year 1963

The Above well was plugged as follows:

211' of 8 5/8" surface pipe, cemented with 225 sacks. Fluid was up in  
hole and 1/4 sack hulls and plug was pushed to 240', cemented through  
drill pipe, with 20 sacks cement. Hole was filled with mud to 40',  
2nd cementing plug, 1/4 sack hulls, cemented with 10 sacks to base cellar.  
Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 8/8/63  
INV. NO. 7542-W