

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued August 21, 1967.

Operator's Full Name Specter Pipe & Supply, Inc.

Complete Address: P. O. Box 169, Russell, Kansas 67665

Lease Name Brown "C" Well No. # 1

Location SE NW NW Sec. 30 Twp. 21 Rge. 13 (E) (W) W

County Stafford Total Depth 3772'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Lynch Casing Pulling Company

Address: Route 4, Great Bend, Kansas 67530 License No. 457

Operation Completed: Hour 10:30AM Day 14th Month Sept. Year 1967

The Above well was plugged as follows:

197' of 8 5/8" surface pipe, cement circulated. 3770' of 5 1/2" long string, cement-
ed with 125 sacks. Plug back T.D. 3615'. Top perforation 3405'. Bottom of the hole
was sanded to 3375', and cemented with 5 sacks, through the dump bailer, with cem-
ent from 3375' to 3335'. 3009' of 5 1/2" long string was recovered from the hole.
Bridge plug was pushed in fluid to 210', bridge plug and rock bridge from 210' to
200'. 8 sacks of cement was mixed in a barrel, and put on plug at 200', through
the dump bailer, and let set over-night. Next day hole was bailed dry, and 17
sacks of cement was added to the plug. Hole was filled with mud to 40', rock
bridge from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

RECEIVED
STATE CORPORATION COMMISSION

Signed: Audie Elving
Well Plugging Supervisor

INVOICED

SEP 15 1967

DATE 9/15/67

INV. NO. 6339-4 CONSERVATION DIVISION
Wichita, Kansas