

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JAN 20 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Quality Supply Company

Complete Address: 6320 Jacqueline, Wichita, Kansas

Lease Name Brown Well No. # C-4

Location SW NE NW Sec. 30 Twp. 21 Rge. 13 (E) (W) W

County Stafford Total Depth 3794'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 11:45AM Day 19th Month Jan. Year 1967

The Above well was plugged as follows:

226' of 8 5/8" surface pipe, cement circulated. 3793' of 5 1/2" long string,
cemented with 100 sacks. This is an open hole. Bottom of the hole was sanded
to 3775', and cemented with 5 sacks, through the dump bailer. 2803' of 5 1/2"
long string was recovered from the hole. Bridge plug was pushed in fluid to
226', bridge plug and rock bridge from 226' to 215'. 6 sacks of cement was
mixed in a barrel, and put on plug at 215', through the dump bailer, and let
set over-night. Next day hole was bailed dry, and 19 sacks of cement was added
to the plug. Hole was filled with mud to 40', rock bridge from 40' to 30',
and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 1/20/67
INV. NO. 4639-11