

15.185.01766.0000 *RP*

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 31 1966
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Petroleum, Inc.

Complete Address: 352 N. Broadway, Wichita, Kansas

Lease Name Essmiller Well No. # A-3

Location SW SE NE Sec. 29 Twp. 21 Rge. 13 (E) (W) W

County Stafford Total Depth 3722'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Pipe Pullers, Inc.

Address: Box 486, Ellinwood, Kansas License No. 462

Operation Completed: Hour 4:00 PM Day 28th Month Jan. Year 1966

The Above well was plugged as follows:

349' of 8 5/8" surface pipe, cemented with 250 sacks. 3713' of 5 1/2" long
string, cemented with 150 sacks. Plug back to 3588'. Top perferation 3388'.
Bottom plug was pushed to 3375', 10' of rock bridge, and cemented with 5 sack
2520' of 5 1/2" long string was recovered from the hole. Fluid was up in the
hole. Bridge plug was pushed in fluid to 300', rock bridge from 300' to 290'.
6 sacks of cement was mixed in a barrel, and put on plug at 290', through
the dump bailer, and let set over-night. Next morning hole was bailed dry,
and 19 sacks of cement was added to the plug. Hole was filled with mud to 40'
rock bridge from 40' to 30', and cemented with 10 sacks to the base of the
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving
Well Plugging Supervisor

DATE 1-31-66
INV. NO. 92663-W