

15.185.01765.0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

FEB 7 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Petroleum, Inc.

Complete Address: 352 N. Broadway, Wichita, Kansas

Lease Name Essmiller Well No. # A-2

Location NE SE NE Sec. 29 Twp. 21 Rge. 13 (E) (W) W

County Stafford Total Depth 3714'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Pipe Pullers, Inc.

Address: Box 486, Ellinwood, Kansas License No. 462

Operation Completed: Hour 4:45 PM Day 4th Month Feb. Year 1966

The Above well was plugged as follows:

356' of 8 5/8" surface pipe, cemented with 250 sacks. 3709' of 5 1/2" long
string, cemented with 150 sacks. Plug back to 3589'. Top perferation 3377',
Bottom plug was pushed to 3370', 50' of sand, and cemented with 5 sacks,
through the dump bailer. 2735' of 5 1/2" long string was recovered from the
hole. Fluid was up in the hole. Bridge plug was pushed in fluid to 275',
rock bridge from 275' to 265'. 3 sacks of cement and 10% calcium chloride
was mixed in barrel, and put on plug at 265', through the dump bailer, and
let set for 2 hours. Hole was bailed dry and 22 sacks of cement was added to
the plug. Hole was filled with mud to 40', rock bridge from 40' to 30', and
cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 2/8/66

INV. NO. 2699-W