

15.185.01764.0001

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

FEB 15 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Petroleum, Inc.

Complete Address: 352 N. Broadway, Wichita, Kansas

Lease Name Essmiller Well No. # A-1

Location SE SE NE Sec. 29 Twp. 21 Rge. 13 (E) (W)W

County Stafford Total Depth 3715'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Pipe Pullers, Inc.

Address: Box 486, Ellinwood, Kansas License No. 462

Operation Completed: Hour 9:00 AM Day 10th Month Feb. Year 1966

The Above well was plugged as follows:

354' of 8 5/8" surface pipe, cemented with 250 sacks. 3705' of 5 1/2" long
string, cemented with 150 sacks. Plug back to 3577'. Top perforation 3383'.
Bottom plug was pushed to 3370', 50' of sand, and cemented with 5 sacks,
through the dump bailer. 2528' of 5 1/2" long string was recovered from the
hole. Fluid was up in the hole. Bridge plug was pushed in fluid to 280',
rock bridge from 280' to 270'. 6 sacks of cement was mixed in barrel, and
put on plug at 270', through the dump bailer, and let set over-night. Next
morning hole was bailed dry, and 19 sacks of cement was added to the plug.
Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented
with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 2/15/66
INV. NO. 2928-W