

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 26 1966  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Petroleum, Inc.

Complete Address: 352 N. Broadway, Wichita, Kansas

Lease Name Keller "A" (Flood Unit # 3-10) Well No. # 3

Location NE NE SE Sec. 29 Twp. 21 Rge. 13 (E) (W) W

County Stafford Total Depth 3761'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Pipe Pullers, Inc.

Address: Box 486, Ellinwood, Kansas License No. 462

Operation Completed: Hour 11:30AM Day 25th Month Jan. Year 1966

The Above well was plugged as follows:

205' of 8 5/8" surface pipe, cemented with 225 sacks. 3761' of 5 1/2" long string, cemented with 125 sacks. Plug back to 3520'. Top perferation 3390'. Bottom plug was pushed to 3380', 10' of rock bridge, and cemented with 5 sacks, through the dump bailer. 1804' of 5 1/2" long string was recovered from the hole. Fluid was up in the hole. Bridge plug was pushed in fluid to 200', rock bridge from 200' to 190'. 30 sacks of cement was pumped on plug at 190', through 186' of 2" tubing. Fluid in the hole was now bailed down to 40', bridge plug and rock bridge from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

NOTICED  
DATE 1/26/66  
INV. NO. 2646-w

Signed: Audie Elving  
Well Plugging Supervisor