

1 050801

Docket No. D-21,340

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-21,061.0001

SW SW NW, SEC. 1, T 21 S, R 14 ~~(W)~~

2970 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5430

Lease Name Morrison Trust Well # 1 SWD

Operator: Energy Three, Inc.

County Stafford 118.24

Name & Address P. O. Box 1505

Well Total Depth 3638 feet

Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 263

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well X D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1:00 pm Day: 22 Month: April Year: 19 86

Plugging proposal received from Mark McCabe

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 3636' PBTD 3484' Perfs at 3434-46'

1st plug sand back to 3380' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 70 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 100 sx cement.

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 2:00 pm Day: 22 Month: April Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 3380' and dumped 5 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 70 sx cement, 10 sx gel 1 sack hulls released 8 5/8" rubber plug and pumped 100 sx cement.

Maximum pressure 400 psi and shut in 150 psi

Remarks: Recovered 2000' 5 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION
APR 28 1986
CONSERVATION DIVISION
WICHITA, KANSAS

INVOICED
observe this plugging.

DATE APR 29 1986

Signed Richard W. Lacey
(TECHNICIAN)

INV. NO. 13569