

To: 1 060824
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-20,689.0000
NW NE SE, SEC. 30, T 21 S, R 13 WXX
2310 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 4678
Operator: LASMO Energy Corp.
Name & Address (Southern States)
2700 E. 51st Street, #480
Tulsa, OK 74105

Lease Name Keenan Well # 4
County Stafford
Well Total Depth 3746 121.75 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 311

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:15 am Day: 6 Month: March Year: 19 86

Plugging proposal received from Clay Duntz

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 3743' Open Hole

1st plug sand back to 3690' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 130 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:15 pm Day: 6 Month: March Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 3690' and dumped 5 sx cement on top of sand through bailer, 2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and 130 sx cement.

Maximum pressure 700 psi and shut in 400 psi

Remarks: Recovered 2700' 5 1/2" casing. Cemented by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED
MAR 10 1986
DATE
INV. NO. 12879

RECEIVED
MAR 10 1986
CONSERVATION DIVISION
Wichita, Kansas

Signed Paul A. Luthi (TECHNICIAN)