

15.195.61784.0060

To: 1 041177
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- Drill completion 5/7/53
SE NE NE, SEC. 30, T 21 S, R 13 W/E
4290 feet from S section line
330 feet from E section line

5-23

TECHNICIAN'S PLUGGING REPORT
Operator License # 5447
Operator: OXY USA Inc.
Name & Address: 110 S. Main, #800
Wichita, KS 67202

Lease Name Pundsack Well # 303
County Stafford
Well Total Depth 3737 121.45 feet
Conductor Pipe: Size feet
Surface Casing: Size 10 3/4 feet 198

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105
Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 3:03 p.m. Day: 23 Month: 5 Year: 1996

Plugging proposal received from Alan Vratil

(company name) Clarke Corporation (phone) 316-886-5665

were: 7" at 3720' w/150 sx cement, CIBP at 3675', Perfs at 3409-3580'

1st plug set CIBP at 3350' with 4 sx cement on top,

2nd plug pump 4 sx hulls, 10 sx gel, 60 sx cement, 12 sx gel, 2 sx hulls, and 150 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3:35 p.m. Day: 23 Month: 5 Year: 1996

ACTUAL PLUGGING REPORT 1st plug set CIBP at 3354' with 4 sx cement on top,

2nd plug pumped 400 lbs. hulls, 10 sx gel, 60 sx cement, 12 sx gel, 200 lbs. hulls and 150 sx cement. Maximum pressure 500 psi and shut in 50 psi.

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 30 1996

CONSERVATION DIVISION
WICHITA, KS

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1945' of 7" casing.

(if additional description is necessary, use BACK of this form.)

INVOICED
(if not) observe this plugging.

DATE JUN 05 1996

INV. NO. 45221

Signed Stephen J. Pfeifer
(TECHNICIAN)