

1 120487

10-23

15.185.01781.0002

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Docket #E-13,372

SE SE NE, SEC. 30, T 21 S, R 13 W/EK

2970 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Pundsack Unit Well # 304W

Operator: OXY USA Inc.

County Stafford 122.29

Name & Address P.O. Box 26100

Well Total Depth 3763 feet

Oklahoma City, OK 73126-0100

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 303

Abandoned Oil Well Gas Well Input Well X SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor C.E. Wood Well Servicing License Number 7089

Address P.O. Box 402, Chase, KS 67524

Company to plug at: Hour: 6:15 p.m. Day: 23 Month: 10 Year: 19 90

Plugging proposal received from Gary Wagner

(company name) OXY USA Inc. (phone) 913-483-6700

were: 4 1/2" at 3597' w/200 sx cement, PBTD 3572', Perfs at 3494-3560' (6 sets)

1st plug run tubing to 3560' and pump 75 sx common cement,

2nd plug perforate casing at 855' and run tubing to 900' and circulate cement

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 8:30 p.m. Day: 23 Month: 10 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug ran tubing to 3640' and pumped in with 75 sx common cement,

2nd plug pulled tubing to 900' and pumped in with 275 sx cement, circulated,

3rd plug squeezed in with 25 sx cement.

Pumping pressure 450 psi and shut in 150 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied, common on bottom. No casing recovery. (if additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED

DATE 11-6-90

Signed [Signature] (TECHNICIAN)

INV. NO. 29837

OCT 31 1990