

1 120298

8-29

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drill Completion Date 4/27/53

NE SE NE, SEC. 30, T 21 S, R 13 W/E

3630 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Pundsack Unit Well # 302

Operator: OXY USA Inc.

County Stafford 121.55

Name & Address P.O. Box 26100

Well Total Depth 3740 feet

Oklahoma City, OK 73126-0100

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 191

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor OXY USA Inc. License Number 5447

Address P.O. Box 26100, Oklahoma City, OK 73126-0100

Company to plug at: Hour: 8:30 a.m. Day: 29 Month: 8 Year: 19 89

Plugging proposal received from Mike Malone

(company name) OXY USA Inc. (phone) 913-483-6700

were: 4 1/2" at 3739' PBTD 3620' Perfs at 3491-3555' (5 sets) Squeezed 4 1/2" @ 704' w/200 sx cement

1st plug sand back to 3440' and dump 5 sx cement on top of sand through bailer, cement

2nd plug pump 100 sx cement down 4 1/2"

3rd plug pump 100 sx cement down 8 5/8" X 4 1/2"

RECEIVED
STATE CORPORATION COMMISSION

JUL 24 1989
9-4-89
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Dick Kapp
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 9:45 a.m. Day: 29 Month: 8 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 1400' and dumped 4 sx cement on top of sand through bailer (bridged),

2nd plug perforated 4 1/2" casing at 790-92', pumped into 4 1/2" casing with 100 sx cement, Pumping pressure 0-600 psi and shut in 500 psi.

3rd plug pumped into 8 5/8" X 4 1/2" annulus with 175 sx cement, Pumping pressure 0-125 psi and shut in 125 psi-not on vacuum.

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. No casing recovery. 4 1/2" squeezed.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 9-6-89

Signed Dick Kapp
(TECHNICIAN)

INV. NO. 25801

8-29