

8-29 15.185.61782.0000

1 120299

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Drill Completion Date 4/9/53

NE NE NE, SEC. 30, T 21 S, R 13 W/E

4950 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Pundsack Unit Well #301

Operator: OXY USA Inc.

County Stafford 121.65

Name & Address P.O. Box 26100

Well Total Depth 3743 feet

Oklahoma City, OK 73126-0100

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 184

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor OXY USA Inc. License Number 5447

Address P.O. Box 26100, Oklahoma City, OK 73126-0100

Company to plug at: Hour: 10:45 a.m. Day: 29 Month: 8 Year: 19 89

Plugging proposal received from Mike Malone

(company name) OXY USA Inc. (phone) 913-483-6700

TOC 228' were: 4 1/2" at 3741' CTBP at 3710' PRTD 3714' Perfs at 3419-3562' Squeezed at 400' w/

1st plug sand back to 3380' and dump 4 sx cement on top of sand through bailer, 250' sx cem.

2nd plug perforate at 800' and pump 100 sx cement down 4 1/2" STATE CORPORATION COMMISSION

3rd plug pump 100 sx cement down 8 5/8" X 4 1/2" annulus. RECEIVED 4 1989

Plugging Proposal Received by Richard Lacey (TECHNICIAN) CONSERVATION DIVISION

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:15 a.m. Day: 29 Month: 8 Year: 1989

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 3419' and dumped 4 sx cement on top of sand through bailer.

2nd plug perforated 4 1/2" casing at 800-02', pumped 100 sx cement, pumping pressure 0-200 psi and shut in 100 psi.

3rd plug pumped into 8 5/8" X 4 1/2" annulus with 100 sx cement, pumping pressure 0-300 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. No casing recovery, squeezed at 400'. (If additional description is necessary, use BACK of this form.)

INVOICED

(old text) observe this plugging.

DATE 9-6-89

Signed [Signature] (TECHNICIAN)

INV. NO. 25803

8-29