

1 120300

8-29 15.185.01770.0001

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

Docket #E-13,372 (cancelled in '83)
API NUMBER 15-Drill Completion Date 12/17/51

SW NE NW, SEC. 29, T 21 S, R 13 W/X
4290 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Pundsack Unit Well # 403

Operator: OXY USA Inc.

County Stafford 120.97

Name & Address P.O. Box 26100

Well Total Depth 3722 feet

Oklahoma City, OK 73126-0100

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 368

Abandoned Oil Well _____ Gas Well _____ Input Well X SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor OXY USA Inc. License Number 5447

Address P.O. Box 26100, Oklahoma City, OK 73126-0100

Company to plug at: Hour: 1 p.m. Day: 29 Month: 8 Year: 19 89

Plugging proposal received from Mike Malone

(company name) OXY USA Inc. (phone) 913-483-6700

were: 5 1/2" at 3713' PBTD 3640' Perfs at 3481-3554' (4 sets) Elevation 1905' GL

Squeezed at 380' w/200 sx cement

1st plug sand 5 1/2" casing back to 3430' and dump 4 sx cement on top of sand through bailer,

2nd plug perforate 5 1/2" casing at 800-02', pump 150 sx cement,

3rd plug pump in 8 5/8" X 5 1/2" annulus with 50 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 2 p.m. Day: 29 Month: 8 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3430' and dumped 5 sx cement on top of sand through bailer,

2nd plug perforated 5 1/2" casing with 800-02', pumped 150 sx cement, pumping pressure 0-400 psi and shut in 200 psi.

3rd plug pumped into 8 5/8" X 5 1/2" annulus with 1/4 bbl. slurry and 2 sx cement.

Pumping pressure 0-2000 psi and shut in 1700 psi. RECEIVED STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. No casing recovery, squeezed at 380'. (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 9-6-89 INV. NO. 25804

8-29

CONSERVATION DIVISION Wichita, Kansas Signed [Signature] (TECHNICIAN)