

1 120292

15.185.01776.0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Drill Completion Date 7/3/53
SW NW NW, SEC. 29, T 21 S, R 13 W/8

TECHNICIAN'S PLUGGING REPORT

4290 feet from S section line
4950 feet from E section line

Operator License # 5447

Lease Name Pundsack Unit Well # 410

Operator: OXY USA Inc.

County Stafford 120.67

Name & Address P.O. Box 26100

Well Total Depth 3713 feet

Oklahoma City, OK 73126-0100

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 360

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor OXY USA Inc. License Number 5447

Address P.O. Box 26100, Oklahoma City, OK 73126-0100

Company to plug at: Hour: 8:30 a.m. Day: 23 Month: 8 Year: 19 89

Plugging proposal received from Mike Malone

(company name) OXY USA Inc. (phone) 913-483-6700

were: 5 1/2" at 3709' PBTD 3670' Perfs at 3484-3542' (4 sets) Elevation 1908' GL

1st plug sand 5 1/2" casing back to 3435' and dump 5 sx cement on top of sand through bailer,

2nd plug pump in 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, and 125 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:45 a.m. Day: 23 Month: 8 Year: 1989

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3435' and dumped 5 sx cement
on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, and 125 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

Pumping pressure 0-500 psi and shut in 300 psi.

AUG 30 1989

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. Recovered 2200' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 9-6-89

Signed Duan Rankin
(TECHNICIAN)

INV. NO. 25725