

1 120293

15.185.61775.0001

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Drill Completion Date 4/13/53

NW SW NW, SEC. 29, T 21 S, R 13 W/E

3630 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Pundsack Unit Well # 409

Operator: OXY USA Inc.

County Stafford 120.71

Name & Address P.O. Box 26100

Well Total Depth 3714 feet

Oklahoma City, OK 73126-0100

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 363

Abandoned Oil Well  Gas Well  Input Well  SWD Well  O&A

Other well as hereinafter indicated

Plugging Contractor OXY USA Inc. License Number 5447

Address P.O. Box 26100, Oklahoma City, OK 73126-0100

Company to plug at: Hour: 11 a.m. Day: 23 Month: 8 Year: 19 89

Plugging proposal received from Mike Malone

(company name) OXY USA Inc. (phone) 913-793-5861

were: 5 1/2" at 3711' CIBB 3500'

1st plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and 125' sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 12:30 p.m. Day: 23 Month: 8 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 125 sx cement.

Pumping pressure 0-500 psi and shut in 300 psi.

RECEIVED STATE CORPORATION COMMISSION

AUG 30 1989

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. Recovered 2600' of 5 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 9-6-89

Signed [Signature] (TECHNICIAN)

INV. NO. 25794