

1 120294

15.185.01773.0001

8-23

Docket #E-13,372(cancelled in '83)
Drill Completion Date 9/21/52

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-

SE SW NW, SEC. 29, T 21 S, R 13 W/E
2970 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Pundsack Unit Well # 407

Operator: OXY USA Inc.
Name & Address: P.O. Box 26100
Oklahoma City, OK 73126-0100

County Stafford 120.77
Well Total Depth 3716 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 361

Abandoned Oil Well _____ Gas Well _____ Input Well X SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor OXY USA Inc. License Number 5447

Address P.O. Box 26100, Oklahoma City, OK 73126-0100

Company to plug at: Hour: 1 p.m. Day: 23 Month: 8 Year: 19 89

Plugging proposal received from Mike Malone

(company name) OXY USA Inc. (phone) 913-483-6700

were: 5 1/2" at 3712' PBTD 3660' Perfs at 3490-3556' (4 sets)

1st plug sand back to 3440' and dump 5 sx cement on top of sand through bailer,
300 lbs. hulls,

2nd plug pump 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and 125 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All x Part _____ None _____

Operations Completed: Hour: 2:30 p.m. Day: 23 Month: 8 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 3440' and dumped 5 sx cement on top of
sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 5 sx gel, and 175 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

Pumping pressure 0-500 psi and shut in 250 psi.

SEP - 4 1989 9-4-89

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. Recovered 400' of 5 1/2" casing
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 9-6-89

Signed Steve Durrant
(TECHNICIAN)

WV. NO. 25802