

15.185.01768.0001

10-23

1 120489

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Drill Completion Date 8/6/51

SW SW NW, SEC. 29, T 21 S, R 13 W/EX

2970 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Pundsack Unit Well # 401

Operator: OXY USA, Inc.

County Stafford 120.93

Name & Address P.O. Box 26100

Well Total Depth 3721 feet

Oklahoma City, OK 73126-0100

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 366

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Ziegler Well Servicing Inc. License Number _____

Address P.O. Box 873, Russell, KS 67665

Company to plug at: Hour: 2 p.m. Day: 23 Month: 10 Year: 19 90

Plugging proposal received from Gary Wagner

(company name) OXY USA, Inc. (phone) 913-483-6700

were: 5 1/2" at 3718' w/150 sx cement; PBD 3593', Perfs at 3404-3557' (7 sets)

1st plug pump 75 sx cement at 3560', 2nd plug cut tubing at 1130', perforate Anhydrite at 875', run tubing to 875' and circulate cement.

Plugging Proposal Received by Steve Durrant

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 6:15 p.m. Day: 23 Month: 10 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug shot tubing at 920', attempted to perforate 5 1/2" casing, hole bridged at 350', went back in with tubing to 770', casing parted at 770',

circulated with 350 sx cement from 770' through tubing. Left 770' of 2 3/8" tubing in well.

Remarks: Used 60/40 Pozmix 6% gel by Allied, common cement on bottom plug. No casing recovery

(If additional description is necessary, use BACK of this form.)

INVOICED

(If possible, observe this plugging.)

DATE 11-6-90

OCT 31 1990

Signed Steve Durrant
(TECHNICIAN)

INV. NO. 29835