

1 090691

15.185.00012.0000

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-Completion Date 8/31/52  
NW SE NW, SEC. 29, T 21 S, R 13 ~~XX~~  
3630 feet from S section line  
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5447  
Operator: OXY USA Inc.  
Name & Address: 110 S. Main, Ste. 800  
Wichita, KS 67202

Lease Name Pundsack Well # 406  
County Stafford  
Well Total Depth 3714 120.70 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 10 3/4 feet 358

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SMD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105  
Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 1:50 p.m. Day: 7 Month: 6 Year: 19 96

Plugging proposal received from Alan Vratil  
(company name) Clarke Corporation (phone) 316-886-5665

work: 7" at 3712' w/150 sx cement, Perfs at 3398-3558, Open hole 3712-14'  
1st plug run tubing and spot 100 sx cement across perfs,  
2nd plug pump 4 sx hulls, 10 sx gel, 60 sx cement, 12 sx gel, 2 sx hulls, release 10 3/4"  
wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 2:25 p.m. Day: 7 Month: 6 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug ran tubing and spotted 100 sx cement across perfs,  
2nd plug pumped 300 lbs. hulls, 10 sx gel, 60 sx cement, 12 sx gel, 100 lbs. hulls, released  
10 3/4" wiper plug and pumped 150 sx cement.

RECEIVED  
KANSAS CORPORATION COMMISSION

Maximum pressure 1000 psi and shut in 50 psi.  
JUN 11 1996

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1897' of 7" casing.  
WICHITA, KS  
(If additional description is necessary, use BACK of this form.)

INVOICED  
DATE JUN 24 1996  
W.D. NO. 45861

Signed \_\_\_\_\_  
(TECHNICIAN)