

To: 1 090694 15.195.01772.0000  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- Drilled 1952  
SE NW NW, SEC. 29, T 21 S, R 13 W/E

6-7-96

4290 feet from S section line  
-4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License / 5447  
Operator: OXY USA Inc.  
Name:  
Address 110 S. Main, Ste. 800  
Wichita, KS 67202

Lease Name Pundsack Well / 405  
County Stafford  
Well Total Depth 3712 120.64 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 10 3/4 feet 366

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A   
Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105  
Address P.O. Box 187, Medicine Lodge, KS

Company to plug at: Hour: 3:15 p.m. Day: 6 Month: 6 Year: 19 96

Plugging proposal received from Alan Vratil  
(company name) Clarke Corporation (phone) 316-886-5665

Work: 7" at 3706' w/150 sx cement, CIBP at 3660', Perfs at 3610-24'  
Casing parted at 544'. Run tubing to 590' and circulate cement to surface.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 5:45 p.m. Day: 7 Month: 6 Year: 19 96

ACTUAL PLUGGING REPORT 6/6/96 Ran tubing to 590' and spotted 150 sx cement-60/40 Pozmix  
6% gel. Lost circulation. Pulled tubing.

6/7/96 Ran back in with tubing and tagged cement at 560'. Spotted 125 sx cement-60/40 Pozmix  
3% cc. Pulled tubing. Let set 4 hours. Ran back in with tubing and tagged at 280'.

labeled cement to surface with 125 sx cement. Stayed full.

KANSAS CORPORATION COMMISSION

JUN 13 1996

Remarks: Used 60/40 Pozmix 6% and 3% gel by Allied. No casing recovery.

(If additional description is necessary, use BACK of this REPORT)

INVOICED  
DATE JUN 24 1996  
INV. NO. 45862

Signed [Signature] (TECHNICIAN)