

To: 1 052043 15.185.01769.0000 API NUMBER 15-

STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

NE SW NW, SEC. 29, T. 21 S, R. 13 W/X

5-15

3630 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Pundsack Well # 402

Operator: OXY USA INC.

County Stafford 12073

Name: 110 S. Main, Ste. 800

Well Total Depth 3715 feet

Address: Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 350

Abandoned Oil Well Gas Well Input Well SMD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 12 p.m. Day: 15 Month: 5 Year: 19 96

Plugging proposal received from Allen Vratil

(company name) Clarke Corporation (phone) 316-886-5665

Work: 5 1/2" at 3711' w/150 sx cement, PBDT 3643', Perfs at 3400-3548', with 250 sx cement
1st plug sand back to 3450' and dump 5 sx cement on top of sand through bailer,

2nd plug run in tubing to 807' and pump 25 sx cement,

3rd plug circulate cement to surface.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2 p.m. Day: 15 Month: 5 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded back to 3450' and dumped 5 sx cement on top of sand through bailer,

RECEIVED KANSAS CORPORATION COMMISSION

2nd plug ran in with tubing to 807' and pumped 25 sx cement,

MAY 21 1996

3rd plug pulled up to 300' and circulated cement to surface with 90 sx.

CONSERVATION DIVISION WICHITA, KS

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery. Cemented in to surface. (If additional description is necessary, use BACK of this form.)

I (PRINT NAME) observe this plugging.

Signed Richard W. Lacey (TECHNICIAN)

DATE JUN 05 1996

INV. NO. 45722