

1052325  
TO: STATE CORPORATION COMMISSION

7-21

API NUMBER 15-185-22,489 <sup>06-00</sup>  
NW SE NE SEC. 29, T 21 S, R 13 W

CONSERVATION DIVISION - PLUGGING SECTION 1650 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 990 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME CONNOR WELL # 1

TECHNICIAN'S PLUGGING REPORT COUNTY STAFFORD

OPERATOR LICENSE # 9408 WELL TOTAL DEPTH 3730 <sup>121.25</sup> FEET

OPERATOR: TRANS PACIFIC OIL CORPORATION PRODUCTION CSG: SIZE 5 1/4" @ 3726' WITH 110 SX

NAME AND 100 S MAIN, SUITE 200 SURFACE CASING: SIZE 8 5/8" @ 298' WITH 190 SX

ADDRESS WICHITA, KS 67202

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD WELL  D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR DS&W WELL SERVICING LICENSE NUMBER 6901

ADDRESS PO BOX 231 CLAFLIN, KS 67525

COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 21 MONTH: 07 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM BRIAN FRENZEL

(COMPANY NAME) DS&W (PHONE) 316-587-3361

WERE: PERFS AT 3726-30

SAND BACK TO 3676' WITH 5 SX CEMENT. PLUG DOWN 8 5/8 300# HULLS, 10 SX GEL, 50 SX CEMENT, 10

SX GEL, 100# HULLS, 8 5/8 WIPER PLUG, & 100 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL  PART  NONE

OPERATIONS COMPLETED: HOUR: 10:10 AM DAY: 21 MONTH: 07 YEAR: 1999

ACTUAL PLUGGING REPORT

SAND BACK TO 3775' AND 5 SX CEMENT.

PUMP DOWN 8 5/8 WITH 300# HULLS - 10 SX GEL - 50 SX CEMENT - 10 SX GEL - 100# HULLS - 8 5/8

WIPER PLUG - 100 SX CEMENT. MAXIMUM PRESSURE AT 500 PSIG. SHUT IN PRESSURE AT 400 PSIG.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1340' OF 5 1/4" CASING  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING  
STATE CORPORATION COMMISSION

RECEIVED  
SIGNED Richard M. Lacy  
(TECHNICIAN) FORM CP-2/3

INVOICED  
DATE 8-5-99

AUG - 3 1900

INV. NO. 60116

CONSERVATION DIVISION  
Wichita, Kansas

(R)