

1 120257

5-12

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,492.0000

SE SE SW, SEC. 29, T 21 S, R 13 N/E

330 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9408

Lease Name Keller Well # 1

Operator: Trans Pacific Oil Corporation
Name & Address 410 One Main Place
Wichita, KS 67202

County Stafford 121.75

Well Total Depth 3746 feet

RECEIVED
STATE CORPORATION COMMISSION
MAY 16 1989
CONSERVATION DIVISION
Wichita, Kansas

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 295

Abandoned Oil Well Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10 a.m. Day: 12 Month: 5 Year: 19 89

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 5 1/2" at 3746' PBTD 3485' Perfs at 3455-59'

1st plug sand back to 3400' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release

8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1 P.m. Day: 12 Month: 5 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3400' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Pumping pressure 0-400 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3000' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
I (Name) observe this plugging.

DATE 5-17-89

Signed Duane Rankin (TECHNICIAN)

INV. NO. 24882