

To: 1 120740 10-7
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

15.195.10097.0002
API NUMBER 15- Docket #D-18,736 230
E/2 NE SE, SEC. 21, T 21 S, R 13 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5310
Operator: Four Way Operating Inc.
Name & Address P.O. Box 698
Great Bend, KS 67530

1980 feet from S section line
330 feet from E section line
Lease Name Sipes Well # 2
County Stafford 108.25
Well Total Depth 2100 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 283

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well X D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Stepco Well Service, Rockhold Engineering License Number 5111
Address P.O. Box 698, Great Bend, KS 67530

Company to plug at: Hour: 9:30 a.m. Day: 2 Month: 10 Year: 1992

Plugging proposal received from Jim Rockhold
(company name) Rockhold Engineering (phone) 316-792-2506

were: 6" casing at 2089' w/150 sx cement, 2" tubing at 1860', packer at 1835', Perfs at 1824-2004'
Run tubing to total depth and circulate cement in 6" casing. Squeeze 100 sx cement
in 6" X 8 5/8" annulus.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 11:30 a.m. Day: 7 Month: 10 Year: 1992

ACTUAL PLUGGING REPORT 10/2/92-ran tubing to 1900' and pumped through tubing with 150 sx cement
Pulled tubing to 915' and pumped in with 150 sx cement while losing returns. Pulled tubing to
700' and pumped in 25 sx cement. Lost returns. Pulled tubing to 610' and pumped in with 75 sx
cement with some returns. Shut down. 10/5/92-ran wireline. Found top of cement at 504'.
10/7/92-ran tubing to 490' and circulated 6" casing and 6" X 8 5/8" annulus with 100 sx cement.
Pulled all tubing and filled with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. No casing recovery.
(If additional description is necessary, use BACK of this form.)

I (did ~~not~~) observe this plugging.

INVOICED
DATE 10-29-92
INV. NO. 36636

STATE CORPORATION COMMISSION
RECEIVED
OCT 12 1992
CONSERVATION DIVISION
Wichita, Kansas
Signed Richard Lacey
(TECHNICIAN)