

To: 1 051367
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

11-16
API NUMBER 15-185-21,003-0000
NE SE SW, SEC. 21, T 21 S, R 13 W/E
990 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 6170
Operator: Globe Exploration Inc.
Name & Address Box 12
Great Bend, KS 67530

Lease Name Harms Well # 1
County Stafford 121.51
Well Total Depth 3739 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 325

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10 a.m. Day: 16 Month: 11 Year: 19 90

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 3730' w/200 sx cement, Perfs at 3703-12'

1st plug sand back to 3650' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11 a.m. Day: 16 Month: 11 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 3650' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped down the 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement

Maximum pressure 250 psi and shut in 50 psi.

RECEIVED
STATE CORPORATION COMMISSION
NOV 20 1990
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1835' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED
DATE NOV 27 1990
INV. NO. 30036

Signed Richard W. Lacey
(TECHNICIAN)