

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-20999-00-00
Spot: CSWSWSE Sec/Twnshp/Rge: 21-21S-13W
330 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: STONE Well Number: 1-C
County: STAFFORD Total Vertical Depth: 3717 feet

Operator License No.: 100
Op Name: KANSAS CORPORATION COMMISSION
Address: 130 S MARKET RM 2078
WICHITA, KS 67202

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 298 WITH 275 SX CMT
Production: Size 5.5 feet: 3706 WITH 175 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 10/09/2002 9:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: RICHARD LACEY Company: KANSAS CORPORATION COMMIS Phone: (620) 225-8888

Proposed Plugging Method: SAND TO 3650' & 5 SX CMT ON TOP OF SAND. FREEPOINT CASING AND PULL TO 780'. SPOT 10 SX GEL - 50 SX CMT. PULL CASING TO 330' & SPOT 50 SX CMT. PULL CASING TO 40' & FILL TO SURFACE WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/09/2002 4:20 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

OPEN HOLE 3706-3717'. CASING HOLES FROM 1000' TO 300'. SANDED TO 3620' & 5 SX CMT WITH DUMP BAILER. RAN TUBING TO 800'. PUMPED 305 SX CMT. LOSS CIRCULATION. PULL OUT OF HOLE WITH TUBING. WOC 4 HOURS. RAN TUBING IN BACK TO 800'. DID NOT TAG CMT. PUMPED 145 SX CMT CIRCULATING CMT TO SURFACE. PULLED TUBING OUT. TOPPED OFF HOLE WITH 15 SX CMT.

RECEIVED
OCT 22 2002
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND ACID. NO CASING RECOVERED.

Plugged through: TBG

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

OCT 18 2002


Form CP-2/B