

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-20950-00-00  
Spot: N2S2NWSE Sec/Twnshp/Rge: 21-21S-13W  
1815 feet from S Section Line, 1980 feet from E Section Line  
Lease/Unit Name: STONE B Well Number: 1  
County: STAFFORD Total Vertical Depth: 3692 feet

Operator License No.: 100  
Op Name: KANSAS CORPORATION COMMISSION  
Address: 130 S MARKET RM 2078  
WICHITA, KS 67202

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 326 WITH 250 SX CMT  
Production: Size 5.5 feet: 3680 WITH 125 SX CMT  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 10/11/2002 10:00 AM

Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.

Proposal Rcvd. from: RICHARD LACEY Company: KANSAS CORPORATION COMMIS Phone: (620) 225-8888

Proposed Plugging Method: SAND TO 3630' & 5 SX CMT ON TOP OF SAND. FREEPOINT CASING AND PULL TO 780'. SPOT 10 SX GEL - 50 SX CMT. PULL CASING TO 350' & SPOT 50 SX CMT. PULL CASING TO 40' & FILL TO SURFACE WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 10/11/2002 11:25 AM

KCC Agent: RICHARD LACEY

Actual Plugging Report:

OPEN HOLE 3680-3692'. PERFS UNKNOWN. FELT LIKE K.C. IS PERFED. CASING HOLES FROM 600' TO 700'. SANDED BOTTOM TO 3370' & BAILED 5 SX CMT ON TOP. RAN TUBING TO 800'. CIRCULATED CMT TO SURFACE UP 5 1/2" & 5 1/2" X 8 5/8" ANNULUS WITH 300 SX CMT. PULLED TUBING OUT OF HOLE. TOPPED OFF HOLE WITH 15 SX CMT.

RECEIVED  
OCT 22 2002  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND ACID. NO CASING RECOVERED.

Plugged through: TBG

District: 01

Signed

Richard W. Lacey

(TECHNICIAN)

OCT 18 2002

Form CB 2/3