

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-20566-00-00
Spot: CN2NWSE Sec/Twnshp/Rge: 21-21S-13W
2310 feet from S Section Line, 1980 feet from E Section Line
Lease/Unit Name: SIPES Well Number: 1
County: STAFFORD Total Vertical Depth: 3694 feet

Operator License No.: 100
Op Name: KANSAS CORPORATION COMMISSION
Address: 130 S MARKET RM 2078
WICHITA, KS 67202

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 285 WITH 250 SX CMT
Production: Size 5.5 feet: 3689 WITH 125 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 10/14/2002 5:00 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.

Proposal Rcvd. from: RICHARD LACEY Company: KANSAS CORPORATION COMMIS Phone: (620) 225-8888

Proposed Plugging Method: SAND BOTTOM & PUMP 5 SX CMT ON TOP OF SAND. FREE POINT PIPE & PULL TO 780' & SPOT 10 SX GEL & 50 SX CMT. PULL PIPE TO 310' & SPOT 50 SX CMT. PULL PIPE TO 40' & FILL TO SURFACE WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY
Date/Time Plugging Completed: 10/14/2002 7:10 PM

WitnessType: Plugging Operations 100% Witnessed (Complete)
KCC Agent: RICHARD LACEY

Actual Plugging Report:

OPEN HOLE 3689-3694'. PERFS AT 3599-3636'. FELT LIKE HIGHER PERFS WERE POSSIBLE. SANDED BOTTOM TO 3100' & DUMPED 5 SX CMT ON TOP OF SAND WITH DUMP BAILER. PUMPED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 800' WITH 10 SX GEL WITH 150# HULLS MIXED IN 50 SX CMT. 2ND PLUG AT 290' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. GOOD CIRCULATION TROUGHOUT JOB.

RECEIVED
OCT 22 2002
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND ACID. RECOVERED 1600' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed Richard W. Lacey

(TECHNICIAN)

OCT 18 2002

Form CP-2/3

MP