

1, 052190

15.185.10635.0000

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- Drilled 1949

NW NE NE, SEC. 21, T 21 S, R 13 W/X  
4950 feet from S section line  
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 3134  
Operator: GLM Company  
Name &  
Address P.O. Box 193  
Russell, KS 67665

Lease Name Hoffman Well # 3  
County Stafford 119.11  
Well Total Depth 3665 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 323

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Quality Well Service License Number 31925  
Address 249 E. Beth Dr., Sterling, KS 67579

Company to plug at: Hour: 12 p.m. Day: 10 Month: 11 Year: 19 97

Plugging proposal received from Richard McIntyre

(company name) Quality Well Service (phone) 316-727-3410

work: 5 1/2" at 3651' w/125 sx cement, Open hole 3651-65'


1st plug sand back to 3600' and dump 5 sx cement on top of sand through bailer,

2nd plug at 750' with 50 sx cement,

3rd plug at 350' with 50 sx cement,

4th plug at 40' with 10 sx cement.

11-18-97



Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 2:30 p.m. Day: 10 Month: 11 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 3600' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 8 sx gel, 50 sx cement, and 2 sx gel at 750',

3rd plug pumped 2 sx hulls and 50 sx cement at 350',

4th plug pumped 10 sx cement at 40'.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2430' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
NOV 24 1997  
DATE  
INV. NO. 49560  
11-10

Signed Richard W. Lacy (TECHNICIAN)