

3-21

2-010135

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER: 15-113-20,814-0000

SW NW SE, SECTION 5 TOWNSHIP 21 RANGE 5W

OPERATOR LICENSE # 9132 1650 FEET FROM S SECTION LINE
OPERATOR MILTON LACKEY 2310 FEET FROM E SECTION LINE
NAME & R.R. 2
ADDRESS INMAN, KS 67456
LEASE NAME: WITTORFF #1
COUNTY: McPHERSON 113.52
WELL TOTAL DEPTH: 3493'
PIPE:
SURFACE CASING: 8 5/8" @ 300'

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: QUALITY WELL SERVICE INC

ADDRESS: 249 BETH DRIVE, STERLING, KS 67579 LICENSE: 31925

COMPANY TO PLUG AT: HOUR: 9:00 DAY: 21 MONTH: 3 YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: MILTON LACKEY

COMPANY NAME: MILTON LACKEY PHONE: (316) 585-2119

WERE: SAND TO 3375' AND TOP WITH 4 SACKS OF CEMENT. SHOOT PIPE OFF. PULL PIPE TO 750' AND SPOT 35 SACKS OF CEMENT. PULL PIPE TO 350' AND CIRCULATE CEMENT TO SURFACE.

4 1/2" CASING AT 3492'

PERFS AT 3426' - 3428'

PLUGGING PROPOSAL RECEIVED BY: MICHAEL R. WILSON

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL { } PART { X } NONE { }

COMPLETED: HOUR: 11:00 DAY: 21 MONTH: 3 YEAR: 1997

ACTUAL PLUGGING REPORT: SANDED TO 3370' AND TOPPED WITH 4 SACKS OF CEMENT. SHOT PIPE OFF AT 2027'. PULLED PIPE TO 743' AND SPOTTED 35 SACKS OF CEMENT. PULLED PIPE TO 372' AND CIRCULATED 108 SACKS OF CEMENT TO THE SURFACE.

RETRIEVED 2027' OF 4 1/2" CASING - 49 JOINTS.

REMARKS: 60/40 POZ 4% GEL UNITED #3068

INVOICED
DATE APR 04 1997
INV. NO. 4785.1

RECEIVED
KANSAS CORPORATION COMMISSION

APR 02 1997

CONSERVATION DIVISION
WICHITA, KS

I DID OBSERVE THIS PLUGGING.

Michael R. Wilson

MICHAEL R. WILSON

FORM CP-2/3

REV. 3/90

DW