

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

2- 010198

6-21 15.113.20010.0000

API NUMBER: 4-1-67

E/2-SE-NW SECTION 28 TOWNSHIP 21S RANGE 3W

OPERATOR LICENSE # 30009

3,316' FEET FROM S SECTION LINE

OPERATOR Randon Production Co.

2,927' FEET FROM E SECTION LINE

NAME & 2761 N. Remington Road

ADDRESS Marion, KS 66861

LEASE NAME: Neufeldt #1

COUNTY McPherson

WELL TOTAL DEPTH: 3,385' 110.01

PIPE:

SURFACE CASING 8 5/8" at 186'

ABANDONED OIL WELL ☒ GAS WELL ☐ INPUT WELL ☐ SWD ☐ D&A ☐

OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: Larry George Sage

ADDRESS: P.O. Box 12 Virgil, KS 66870 LICENSE: #5684

COMPANY TO PLUG AT: HOUR: 09:00 DAY: 14 MONTH: 6 YR: 1999

PLUGGING PROPOSAL RECEIVED FROM: George Sage

COMPANY NAME: Larry George Sage PHONE: 316-678-3440

WERE: Sand to 3,050' and top with 5 sxs. cement. Shoot pipe off. Pull pipe to 550' and spot 35 sxs. cement. Pull pipe to 275' and circulate cement to the surface.

5 1/2" casing at 3,375'.

Perforations from 3,104' to 3,114'.

PLUGGING PROPOSAL RECEIVED BY: Michael R. Wilson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (☒) PART (☐) NONE (☐)

COMPLETED: HOUR: 11:00 DAY: 21 MONTH: 6 YEAR: 1999

ACTUAL PLUGGING REPORT: Sanded to 3,050' and topped with 5 sxs. cement. Tried to pull 5 1/2" pipe but parted at 277.40'. Tried to screw into 5 1/2" casing-no luck. Perforated casing at 550' with 3 shots. Ran 2 3/8" tubing to 290' and hit bridge-worked through bridge and finished running tubing to 540' and spotted 35 sxs. cement. Pulled tubing to 270' and circulated 140 sxs cement to the surface. Retrieved 277.4' of 5 1/2" casing (9 jts.).

REMARKS: Used 60/40 posmix by George Sage. Invoice #2R.

INVOICED

DATE 6-28-99

INV. NO. 61097

I DID OBSERVE THIS PLUGGING.

Michael R. Wilson

FORM CP-2/3
REV. 3/90