

02-010198

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-113-30198-00-00 Spot: E2SENW  
Sec: 28 Twnshp & Dir: 21 S Rng & Dir: 3 W  
Feet: 3316 frm N/S: S Feet: 2927 frm E/W: E  
Lease/Unit Name: NEWFELDT Well Number: 1  
County: MCPHERSON Total Vertical Depth: 3385 feet

Operator License No.: 30009  
Operator Name: Randon  
Address: 2761 N. Remington Rd.  
Marion, KS 66861

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 186 11001  
Production: Size 5.5 feet: 3375

Well Type: OIL UIC Docket No: Date/Time to Plug: 06/14/1999 9:00 AM

Plug Co. License No.: 5684 Plug Co. Name: Sage, Larry George

Proposal Received from: Larry George Sage Company Name: Sage, Larry George

OpRepPhoneNo: (316) 678-3440

Were: Sand to 3,050' & top w/5 sxs.cement. Shoot pipe off,pull pipe to 550' & spot 35 sxs cem. Pull pipe to 275' & circulate cem.to surface 5 1/2" casing@ 3375' Perf from 3104' to 3114'

Plugging Proposal Received By: Michael R. Wilson,KCC WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 06/21/1999 11:00 AM

Actual Plugging Report:

Sanded to 3050' & topped w/5sxs.cem.Tried to pull 5 1/2"pipe-parted @277.40'.Perf.casing @ 550'w/3 shots. 2 3/8" tubing to 290' &hit bridge.Finished tub. to 540' &spotted 35 sxs cem.Pulled tubing to 270'& cir.140 sxs.cem.to surf. Retrieved 277.4'of 5 1/2"

Remarks: Inv # 2R 60/40 poxmix by George Sage SEE PA FILE FOR MORE DETAILED INFO.ON PLUGGING

Anhydrite Plug: No BottomPlug:  DakotaPlug: No

Plugged through:

I (did) did not observe this plugging.

**INVOICED**

DATE 10/7/99

INV. NO. 100948

Signed

(TECHNICIAN)