

STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - Plugging Section
 130 S. Market, Room 2078
 Wichita, Kansas 67202

15-113-30198-00-00-

API NUMBER: 4-1-67

E/2-SE-NW SECTION 28 TOWNSHIP 21S RANGE 3W

OPERATOR LICENSE # 30009
 LINE OPERATOR Randon Production Co.
 LINE NAME & 2761 N. Remington Road
 ADDRESS Marion, KS 66861

3,316' FEET FROM S SECTION

2,927' FEET FROM E SECTION

LEASE NAME: Neufeldt #1
 COUNTY McPherson
 WELL TOTAL DEPTH: 3,385'
 PIPE:
 SURFACE CASING 8 5/8" at 186'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: Larry George Sage

ADDRESS: P.O. Box 12 Virgil, KS 66870 LICENSE: #5684

COMPANY TO PLUG AT: HOUR: 09:00 DAY: 14 MONTH: 6 YR: 1999

PLUGGING PROPOSAL RECEIVED FROM: George Sage

COMPANY NAME: Larry George Sage PHONE: 316-678-3440

WERE: Sand to 3,050' and top with 5 sxs. cement. Shoot pipe off. Pull pipe to 550' and spot 35 sxs. cement. Pull pipe to 275' and circulate cement to the surface.

5 1/4" casing at 3,375'.

Perforations from 3,104' to 3,114'.

PLUGGING PROPOSAL RECEIVED BY: Michael R. Wilson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 11:00 DAY: 21 MONTH: 6 YEAR: 1999

ACTUAL PLUGGING REPORT: Sanded to 3,050' and topped with 5 sxs. cement. Tried to pull 5 1/4" pipe but parted at 277.40'. Tried to screw into 5 1/4" casing-no luck. Perforated casing at 550' with 3 shots. Ran 2 3/8" tubing to 290' and hit bridge-worked through bridge and finished running tubing to 540' and spotted 35 sxs. cement. Pulled tubing to 270' and circulated 140 sxs cement to the surface. Retrieved 277.4' of 5 1/4" casing (9 its.).

REMARKS: Used 60/40 posmix by George Sage. Invoice #2R.

I DID OBSERVE THIS PLUGGING.


 Michael R. Wilson