

1030247

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-20,760.0000

NE SW SW , SEC. 8 , T 21 S, R 11 W/X
990 feet from N SE Corner of XXX section line
4290 feet from W SE Corner of XXX section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lease Name Keeler B Well # 2

Operator: F. G. Holl

County Stafford

Name & Address 6427 East Kellogg

Well Total Depth 3516 114.2' feet

Wichita, KS 67208

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 283

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 10:00 am Day: 13 Month: August Year: 1984

Plugging proposal received from Mike Gomez

(company name) Kelso (phone) 316-938-2457

were: Perfs 3451-54' 3405 4 1/2" set at 3515'

1st plug sand back to 3350 and dump 4 sx cement on top of sand through bailer

2nd plug pump 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump an additional 125 sx cement

Plugging Proposal Received by Steve DuPont
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 12:00 pm Day: 13 Month: August Year: 1984

ACTUAL PLUGGING REPORT Perfs 3451'-54' 3405' 4 1/2" set at 3515'

1st plug sanded back to 3350' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped an additional 125 sx cement.

Maximum pressure 500 psi and shut in pressure 200 psi

RECEIVED
STATE CORPORATION COMMISSION

AUG 16 1984

Remarks: They recovered 2950' 4 1/2" casing. Cemented by Allied.
(if additional description is necessary, use BACK of this form.)

INVOICED
I (taxpayers) do not observe this plugging.

DATE 8-17-84

Signed Steve DuPont
(TECHNICIAN)

INV. NO. 3198
8-13