

1 060523

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,198.0000  
E/2 E/2 E/2, SEC. 8, T 21 S, R 11 W/E  
2640 feet from S section line  
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5056  
Operator: F. G. Holl  
Name & Address 6427 East Kellogg  
Wichita, KS 67207

Lease Name Rohar Well # 4-8  
County Stafford 115.70  
Well Total Depth 3560 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 299

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&AX \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sterling Drilling Co. License Number 5142  
Address Box 129, Sterling, KS 67579

Company to plug at: Hour: 11:30 pm Day: 22 Month: March Year: 19 85

Plugging proposal received from Vaughn Thompson  
(company name) Sterling (phone) 316-278-2131

were: to fill hole with heavy mud and spot cement through drill pipe  
1st plug at 720' with 50 sx cement  
2nd plug at 510' with 50 sx cement  
3rd plug at 330' with 50 sx cement  
solid bridge  
4th plug hulls - plug at 40' -- cement to surface with 10 sx cement  
6th plug to circulate rat hole with 15 sx cement  
Plugging Proposal Received by Paul A. Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X  
Operations Completed: Hour: 1:45 am Day: 23 Month: March Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 720' with 50 sx cement, 2nd plug at 510' with 50  
sx cement, 3rd plug at 330' with 50 sx cement, 4th & 5th plugs - solid bridge- hulls -  
plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with  
15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

MAR 28 1985

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton  
(If additional description is necessary, use BACK of this form.)

INVOICED  
DATE 4-3-85  
INV. NO. 7505

Signed Paul A. Luthi  
(TECHNICIAN)