

1 100050

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,179.0000

SE NW SW, SEC. 3, T 21 S, R 14 W/E

1500 feet from XYS section line

4290 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5565

Lease Name Asher Well # 1

Operator: National Cooperative Refinery Asso
Name & Address: P. O. Box 6
Graet Bend, KS 67530

County Stafford 118.53

Well Total Depth 3647 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 846

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Allen Drilling Company License Number 5418

Address Box 1389, Great Bend, KS 67530

Company to plug at: Hour: 9:00 am Day: 18 Month: March Year: 19 85

Plugging proposal received from Don Kern

(company name) Allen (phone) 316-793-5681

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 900' with 50 sx cement

2nd plug at 450' with 50 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Phyllis Wiley
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 11:00 am Day: 18 Month: March Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 900' with 50 sx cement, 2nd plug at 450' with
50 sx cement, 3rd & 4th plugs - solid bridge- hulls - plug at 40' -- cement to surface
with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement

RECEIVED
STATE CORPORATION COMMISSION

MAR 25 1985

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun

(if additional description is necessary, use BACK of this form.)

Signed Phyllis Wiley
(TECHNICIAN)

INV 10102
DATE 3-26-85
INV. NO. 17450
I (did not) observe this plugging.