

To: 1052105
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-185-21,086.0000
50' NE of
SE NE SE, SEC. 3, T 21 S, R 14 W/E
App. 1675 feet from S section line
App. 305 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License / 30705
Operator: Younger Energy Company
Name & Address
453 S. Webb Rd., Ste. 100
Wichita, KS 67207

Lease Name Nina Davis Well # 1
County Stafford 118.88
Well Total Depth 3658 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 353

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor D S & W Well Servicing, Inc. License Number 6901
Address P.O. Box 231, Claflin, KS 67525-0231

Company to plug at: Hour: 9 a.m. Day: 30 Month: 1 Year: 19 97

Plugging proposal received from Kent Strube
(company name) D S & W Well Servicing, Inc. (phone) 316-587-3361

were: 5 1/2" at 3656' w/75 sx cement, Open hole 3656-58'

Attempted to run tubing to bottom, got to 1122' with much difficulty. Spot cement through tubing:

1st plug at 1121' with 25 sx cement and 100 lbs. hulls,

2nd plug at 913' with 75 sx cement, 3rd plug at 853' with 250 sx cement,

4th plug at 365', circulate cement to surface. 24.97

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 3 p.m. Day: 31 Month: 1 Year: 19 97

ACTUAL PLUGGING REPORT Spotted cement through tubing:

1st plug at 1121' with 25 sx cement and 100 lbs. hulls,

2nd plug at 913' with 75 sx cement-lost circulation. Waited 24 hrs. Tagged cement at 875'.

3rd plug pulled tubing to 853', pumped 250 sx cement. Good circulation. Tubing stuck. Got out at 210'. Ran tubing.

4th plug tagged cement at 365' and circulated cement with 75 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 495' of 5 1/2" casing-120' had bad corrosion.
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED
DATE FEB 10 1997
INV. NO. 47538

Signed Richard W. Lacey
(TECHNICIAN)